



TYPICAL SECTION A-A

NOTES:

1. FABRIC FOR WRAPPING THE DRAINS WITH PERFORATED PIPE AND WASHED STONE SHALL BE THE NON-WOVEN TYPE, MIRAFI 140NL OR EQUAL
2. SUBSURFACE DRAINAGE SHALL BE INSTALLED IN ALL MEDIANS WHERE DRAIN LINES CAN BE TIED INTO EXISTING STORM DRAIN SYSTEM. A 4 INCH PERFORATED, CORRUGATED PVC DRAIN SHALL BE INSTALLED IN EACH MEDIAN AT THE BOTTOM OF THE EXCAVATED AREA. DRAIN SHALL BE COVERED WITH A MINIMUM 6 INCHES OF #57 WASHED STONE, THEN WRAPPED WITH THE SPECIFIED NON-WOVEN GEOTEXTILE FABRIC. SPECIAL CARE SHALL BE EXERCISED WHEN FILLING MEDIANS WITH SOIL SO NOT TO CRUSH OR DAMAGE THE DRAINAGE SYSTEM OR RECOMPACT THE SOIL.



TOWN OF MOORESVILLE

STANDARD DETAIL

LANDSCAPE STANDARDS
STREET MEDIAN
EXCAVATION, DRAINAGE
AND BACKFILL

January 2012

Revision 2

NTS

L - 7.0